

TSP 301
TECHNICAL SPECIFICATIONS
FOR
TRAFFIC SIGNAL INSTALLATIONS IN THE
CITIES OF MARYVILLE & ALCOA, TN

EQUIPMENT

In addition to any requirements put forth by the State of Tennessee (TDOT) for signalized intersections, the following are required for traffic signal equipment installations in the Cities of Maryville & Alcoa, TN.

3.01 Signal Control Equipment

The standard signal controller for use in the Cities of Maryville & Alcoa is the **PEEK ATC-1000**, configured for use as a **TS2-Type 2** controller in a TS1 cabinet (standard TDOT spec cabinet). The PEEK ATC-1000 shall include a multi-mode fiber module for communications.

If a NEMA TS2-Type1 cabinet is required (see section 3.02), the standard controller will be a **PEEK ATC-1000**, configured for **TS2-Type 1** operation.

It shall be the contractor's responsibility to ensure that the most current firmware is installed on the controller.

The standard conflict monitor unit shall be a **PEEK SG1000** configured for either TS1 or TS2-Type1 operation as necessary.

3.02 Controller Cabinet

The following specifications apply to both **NEMA TS2- Type 1** cabinets, and **NEMA TS-1** cabinets:

Both TS1 and TS2-Type1 shall be a **P44 enclosure type** with the following interior components: 2 shelves, LED lighting, 1 fan, 1 thermostat, and 12"x16" Air filter.

IF a video detection system is to be installed, the cabinet shall not have loop detector racks, or harnesses.

The metering device for the cabinet electricity shall be installed on the pole which the power service is dropped to if power is an overhead service. If power is fed from underground service, meter shall be mounted to "unistrut" style rigid brackets which shall be cast into the cabinet foundation, unless other arrangement is specified.

The cabinet base foundation will include a poured pad/ work platform in front of the door at ground level.

Any work associated with installation of the controller, conflict monitor, loop detectors, wiring, etc. or power up/set-up shall be included in the unit price bid for this item.

All controller cabinets shall be installed with the door opposite the intersection so that the signal technician will have a view of the intersection while facing the equipment.

3.02.01 NEMA TS1 cabinets

NEMA TS1 cabinets shall have **12 Phase load bays, a TS2 Type 2 Controller Interface, NEMA TS1 CMU, and A,B, and C connectors.**

3.02.02 NEMA TS2-Type 1 cabinets

NEMA TS2-Type 1 cabinets shall have **16 phase load bays, TS2 Type 1 Controller Interface, NEMA TS2 MMU, and NO B and C connectors.**

MATERIALS

In addition to the requirements of TDOT and the Manual on Uniform Traffic Control Devices, the following are requirements for traffic signal materials in the Cities of Maryville and Alcoa.

3.03 Signal Displays

All signal displays shall be incandescent look signal lamps. LED modules are to be included in the price for items “MACTO 730-02.xx Signal Head Assembly L.E.D.”

All signal heads shall be of cast aluminum, color yellow.

Signal head assemblies shall include **Pelco’s AeroFlex** (BK-8000-#-PNC) or approved equivalent dull black backplates with a retro-reflective border.

Pedestrian displays shall be a single section, LED, cast aluminum, yellow, hand/man displays with a countdown timer.

Pedestrian pushbuttons shall be accessible type, meeting all current MUTCD, PROWAG requirements.

The following are approved mounting methods for signal heads:

Span Wire Installations: Pelco or compatible quick disconnect hanger.

(Wiring schematic available on request.)

Mast Arm Installations: Astro Brac or compatible rigid mount.

3.04 Signal Wiring

Signal cable shall have a minimum of one spare conductor after installation.

For phases using 3 section heads a five-conductor cable shall be used per phase.

For phases using 5 section heads a seven conductor cable shall be used.

3.05 Fiber Optic Cable

Multi-mode type fiber optic cable shall be 50 μm core diameter, with at least 12 fibers per cable unless otherwise specified in the plans. Single-mode type cable shall be between 8-9 μm core diameter, with at least 12 fibers per cable unless otherwise specified. A fiber optic drop cable shall be a minimum of 6 fibers (each type) and be spliced into the trunkline in a splice enclosure either aurally or in a pull box. Contractor shall provide 50ft of slack either lashed to a span aurally, or coiled in a pull box for underground installations. Termination panels shall be provided with sufficient size to provide for a neat installation, and enough panel space to accommodate the specified number of fibers for termination. ST connectors shall be used on the termination panel unless otherwise specified. Contractor shall provide any necessary jumpers for installed equipment.

3.06 Video Detection

The following video detection units are approved for use in the cities of Alcoa and Maryville:

- 1) Gridsmart

Substitutions will be considered on a case by case basis. The brand or type of video detection will be determined in the project plans. Video detection units shall be capable of providing color video monitoring and be IP addressable with an Ethernet port provided for remote configuration and streaming video.

3.07 Removal of Signal Equipment

Signal controller equipment, signal displays/wiring, loop detectors, cabinet and wiring, span wires, mast arm poles, etc to be removed from the site shall be returned to MACTO. Care should be taken to avoid damaging equipment. Removal of Signal Equipment includes removal of strain poles, controller cabinets and foundations, and any concrete foundations supporting mast arms or strain poles to a depth of 2 ft below finished grade.

3.08 Ethernet Switch

All ethernet switches shall be hardened and unmanaged with two (2) small form-factor pluggable (SFP) ports as well as a minimum of six (6) gigabyte ethernet ports.

SFP transceiver modules shall be compatible with single-mode fiber and have LC connectors.

All ethernet switches shall function on 1310 nm wavelength and contain any necessary hardware to bring into full operation.

INSTALLATION OF TRAFFIC SIGNAL EQUIPMENT

3.09 Requirements for New Signal Installations

All new signal displays shall be covered with a durable black bag when not operational. It shall be the contractor's responsibility to ensure that signal displays remain covered and that covers do not become worn & tattered before final removal.

QUALIFIED PERSONNEL

3.10 Requirements for Certification of Personnel

For installation of any traffic control device or equipment, an IMSA Level II (or higher) certified technician shall supervise all activities. The certified technician shall be present on the site while work is being performed.

3.11 Proof of Certification

Proof of IMSA certification shall be required in the form of a certification card accompanied by photo ID.